



***Implementation of Automation, SCADA &
PLC based control System and related
services for Treated water pumping station
& Power management system for Saidabad
Water Treatment Plant Phase-1***

PREPARED AND PRESENTED BY
SWTP TEAM




OBJECTIVE

- Implementation of Automation System by integrating PLC, Modules, HMI, Sensors, Actuators and SCADA based Monitoring System at SWTP Phase-1.
- Increasing plant operation efficiency by implementing Automation System similar to SWTP-2, PJWTP, SKWP.
- Reduced the operational downtime by implementing the proper maintained through Automation system.




LAYOUT OF PROPOSED TOTAL AUTOMATION SWTP PHASE-1



- ◆ Implementation
- ◆ Under Implementation
- ◆ Proposed




COMMUNICATION FLOW DIAGRAM OF CENTRAL SCADA SYSTEM






LAYOUT OF SCADA & AUTOMATION OVERVIEW SWTP PHASE-1



DASHBOARD OF PROPOSED TREATED WATER PUMPING STATION

HMI



TOUCH



SCOPE OF WORK

☐ ***Implementation of Automation, SCADA system for Treated Water Pumping Station***


- Treated Water Storage Tank- A & B
- Treated Water Pumping Station- 5 Fixed (355 KW) & 2 Variable speed (375 KW) Horizontal Pump-motor & others equipment.
- Online analyzer (Treated Water)

☐ ***Implementation of Automation, SCADA system for Energy Monitoring System for DPDC & Generator***

- Electrical Substation [2x1600 KVA & 1x1250 KVA] & HT – LT Panel
- Energy Monitoring system for SWTP Phase-1 Generator [1x1.4 MW & 3x1.0 MW] 4.4 MW Power Plant.



TREATED WATER PUMP STATION (SCADA VIEW)





AUTOMATION CONCEPT

AUTOMATION OF TREATED WATER PUMPING STATION

- A. Full automation of existing 5 auto transformer starter pumps and 2 VFD starter pumps along with all other utilities in treated water pumping station with all required safety interlocking. Automatic /Semi-auto selection of pump service or standby mode.
- B. Tank A and Tank B new ultrasonic level sensors (3x) feedback
 - Control Logic:
 - Tank Level < 1.5m : All Pumps off
 - Tank Level 1.5m to 4.5m : All service pumps ON
 - Tank Level > 4.5m : All service pumps ON and Turn off Raw Water
- C. Sump tank existing float switch interlock for High Level and Low Level
 - Control Logic:
 - Tank C above High Level: Turn off Raw Water
 - Tank C below Low Level: Turn off all treated water output pumps
- D. Pump speed control using existing ABB VFD to maintain desired discharge pressure setpoint (3.1 to 3.5 bar)
 - Control Logic:
 - Closed Loop PID control of pump speed using pressure sensor feedback (point F)
- E. Feedback from existing pressure sensors for discharge pressure and network pressure.
- F. Motor Temperature, Vibration and Sound combo sensor installed on each pump (3x per pump, 21 in total)



AUTOMATION CONCEPT


AUTOMATION OF TREATED WATER PUMPING STATION

- G. Control of existing (1200mm dia) motorized valve position from HMI and SCADA
- H. Feedback of actual valve position to HMI and SCADA
- I. Output flow rate feedback from existing flow meter. Automatic alarm in case of low flow (blockage). Feedback to chlorination PLC.
- J. Endress+Hauser residual chlorine monitoring and pH monitoring sensors. Feedback to chlorination PLC.
- K. Interlocks for automatic blower control and Axial fans along with status monitoring.
- L. Endress+Hauser turbidity sensor
- M. Ultra-Sonic level sensor for Sump Tank continuous level measurement
- N. Pressure sensors before and after each pump
- O. Existing Drain Pit pump control using feedback from existing float switches
- P. Sensor box installed on each valve for open/closed position feedback



AUTOMATION CONCEPT


Energy Monitoring System for 11kv sub station & Generator





AUTOMATION CONCEPT

Energy Monitoring System for 11kv sub station & Generator





ENERGY MONITORING SYSTEM (DASHBOARD)





ENERGY MONITORING SYSTEM (DASHBOARD)





TREATED WATER PUMPING STATION & MCC ROOM





HT SWITCH GEAR PANEL





GENERATOR CONTROL PANEL





GAS GENERATOR A1, A2, A3





PRICES PROPOSAL DIFFERENT SUPPLIER

Sl. No.	Description of item	Qty	Rate by Contractors		
			M/S Nasco power Engineering(TK.)	M./S Active International (TK)	M./S Faisal Enterprise (TK)
			total tk.	total tk.	total tk.
1	Treated water pumping station & energy monitoring system	31	41482548.80	42320580.08	41901564.44
	Total Taka		41482548.80	42320580.08	41901564.44
	Rank		1 st lowest	3 rd lowest	2 nd lowest

Attached [Technical Specification of Treated Water & Energy Monitoring Automation System](#) Details



RECOMMENDATION

It is recommended for implement of automation system of Treated Water Pumping Station and Energy Monitoring System of DPDC & Generator for smooth operation of the pump motor and avoid unwanted breakdown of the pump motor.



OUTCOME

- Improved operational efficiency of the treatment plant.
- Synchronization among different stations (i.e.: raw water, filter gallery, treated water etc. and phase-2) for smooth operation of the plant.
- With Improved automation system, SWTP-1 can exceed the designed production capacity of the plant.



CHALLENGES

- Budget & Tender procedure.
- Spare parts not available in local market.
- Upgrading existing system without shutdown of the plant.



THANK YOU
DISCUSSION & DECISION